

Design Standards Letter

Letter Number: G-1971-08

Letter Date: 04/08/1971

Effective Date: 05/01/1971

Section/Plan No.: S0307, S0502, S0614, S0703, S0901, S1050

Subject: Revised Form SP-14 and General Special Provisions

Body

ALL DIVISION AND DISTRICT ENGINEERS

Attached is a revised copies of Form SP-14 dated May, 1971. This form voids the form dated April, 1971.

The revised form incorporates the following changes:

Additions

1. Section 307. Lime Treated Base - Standard Specifications are revised to clarify responsibilities when two-stage mixing is allowed. Also, the 72-hour allowed delay is to apply between initial mixing and final compaction rather than between initial mixing and final mixing.
2. Section 614.20. Automatic Floodgate - entire specification rewritten. Use of Standard Drawing 614.20A Floodgates is discontinued with this specification.
3. Section 703. Concrete Masonry Construction - specification on roadway finish is modified to agree with changes being made in Section 502. Portland Cement Concrete Pavement.
4. Section 901. Highway Lighting - specification is amended to add poles and appurtenances for 45' mounting heights.
5. Section 1050. Lumber, Timber, Piling, Posts and Poles - specification has been revised to correspond with current AWPA practices.

Revisions

1. Section 502. Portland Cement Concrete Pavement - the previous revisions dated January, 1971 have been amended to add texturing by use of a wire comb.

Attached to this letter are copies of these added and revised specifications along with revised

sheets 1, 2, 3, & 4, giving brief descriptions of the General Special Provisions updated to include these additions and revisions for the replacement of similar sheets issued with General Letter No. 4, 1971.

These specifications have been dated May, 1971, and will be effective for projects advertised for the May Letting.

James F. Roberts
Division Engineer
Surveys and Plans