

Design Standards Letter

Letter Number: **G-1985-04**

Letter Date: **11/06/1985**

Effective Date: **01/01/1986**

Section/Plan No.: **S0203, S0802, S0806**

Subject: **Revised General Special Provisions and Form SP-14**

Body

Attached are copies of revised Form SP-14 and General Special Provisions.

All previous General Special Provisions have been included in the 1986 Edition of the Missouri Standard Specifications for Highway Construction except those shown on the revised Form SP-14. The 1986 edition of the standard specifications will be effective with the January 1986 letting.

Some of the revisions included in the new specifications book are as follows:

Sec. 203. The method of measurement for compacting in cuts has been revised and will be measured to the nearest 0.1 Station.

Sec. 802. Mulch overspray has been included in a new item, Type 3 mulch. Separate payment for mulch overspray will not be required. Payment for asphalt emulsion will be included in the pay item for Type 2 Mulch.

Sec. 806. Type I Netting (Jute) has been deleted and Type III Netting has been changed to Plastic Netting. Excelsior blanket has been moved from Sec. 802 to this section.

The following Bid Item Numbers have been added to the Computer listing effective with the January 1986 letting. A new updated list will be printed after the November 1985 letting.

202-10.51 1.0 Lin. Ft. Removal and storage of Existing Bridge Rail

202-10.52 1.0 Lin. Ft. Curb Removal (Bridges)

202-10.53 1.0 Lin. Ft. Curb Removal for Thrie

Beam Installation

202-10.54 1.0 Lin. Ft. Replacement of Expansion Device and Adjacent Concrete

202-10.55 1.0 Lump Sum Partial Removal of Sub-structure Concrete

202-30.07 1.0 Sq. Ft. Seal Coat Removal (Bridges)

202-30.08 1.0 Sq. Ft. Asphalt Removal Bridges)

203-70.75 0.1 Station Compacting in Cut

409-20.92 1.0 Ton Cover Aggregate, See Special Provisions

703-42.16 1.0 Sq. Ft. Slab and Safety Barrier Curb on Concrete I-Girder, See Special Provisions

703-50.40 1.0 Sq. Ft. Modified Deck Repair

712-32.00 1.0 Each Removing, Painting, and Reinstalling Light Standards (Bridges)

802-30.00 0.1 Acre Type 3 Mulch

806-40.00 1.0 Sq. Yd. Plastic Netting

903-71.01 1.0 Each Pull Box, Type A