

Design Standards Letter

Letter Number: **G-1992-13**

Letter Date: **08/19/1992**

Effective Date: **08/19/1992**

Section/Plan No.: **Pay Items**

Subject: **Type 2 Preformed Marking Tape**

Body

Due to the very poor performance of the Type 2 Preformed Marking Tape which was placed during the past few construction seasons, the Construction Division is requesting that it not be specified in any future construction projects.

For projects in the August and September bid openings, the main office will insert the following job special provision:

Type 2 Preformed Marking Tape

Where Type 2 Preformed Marking Tape is specified, the contractor shall substitute Type 1 Preformed Marking Tape, or thermoplastic marking material, or other materials meeting the approval of the engineer. Payment will be made at the price bid for Type 2 Preformed Marking Tape.

For projects after the September bid opening, please specify either Type 1 Preformed Marking Tape, or Thermoplastic Marking Material with the following pay items:

Item Unit Type Item Description

620-99.51 0.1 100 FT. Thermoplastic Marking Material, 4 in., Solid White

620-99.52 0.1 100 FT. Thermoplastic Marking Material, 4 in., Intermittent White

620-99.53 0.1 100 FT. Thermoplastic Marking Material, 4 in., Solid Yellow

620-99.54 0.1 100 FT. Thermoplastic Marking Material, 4 in., Intermittent Yellow

do/kd