

Design Standards Letter

Letter Number: G-1998-04

Letter Date: 04/01/1998

Effective Date: 04/01/1998

Section/Plan No.: S0105, S0107, S0403, S0411, S0616, S0620, S0622, S1000, S1018, S1019, S1045

Subject: Revisions to Job Special Provisions

Body

Effective for April Bid Opening are revisions, additions and deletions to the Support Center Job Special Provisions. The following listing shows the changes made since February postings on the JSP database.

REVISIONS:

MISCELLANEOUS

Supplemental Revisions DSP-98-04C 05/98
SUPPREV

Added revisions to Sec 613 addressing partial pavement repair (MSP-98-06) (Revision C).

DEMOLITION & REMOVAL PROPOSALS

Demolition and Asbestos Removal DEM-97-09A 05/98
DEMASB

Revised Section A, item #3, Method of Bidding by attaching a revised Method of Bidding.

SEC 105 - Control of Work

Construction Surveys DSP-92-03 09/92
CONSTSUR

It is no longer desired for contractors to perform surveys. If it is determined that Construction does not have the resources to perform this task, then the district should arrange a separate contract for a consultant to perform the required surveying on hourly basis.

SEC 107 - Legal Relations & Responsibilities to the Public

General - Federal DSP-90-10U 04/98

FEDERAL

General - State DSP-90-09M 04/98

STATE

Revised for new Blue Pack and Standard Plans effective April 1998.

SEC 403 - Asphaltic Concrete Pavement

Material Transfer Vehicle-Paver Attached DSP-91-03A 05/98

MTVPA

Power-attached MTVs have demonstrated limited success. Although standard specifications do not prohibit their use, they should only be required on an individual project basis. Consult with Construction or Materials for current development of these machines prior to using this DSP.

Material Transfer Vehicle - Independent of Paver DSP-93-31C 05/98

MTV10P

An MTV should be required on projects with significant tonnage (at least 2000 tons) and enough continuous paving to make effective use of these large machines (at least one half mile). Projects in areas dominated by drum plants or batch plants using surge bins should be considered for an MTV requirement since surge bins are often linked to mix segregation .

Large Stone Binder MSP-92-02C 06/98

MSP0202C

Bituminous Mixture QC/QA MSP-96-01H 06/98

MSP9601H

Limited use. Only as approved by Materials Division.

SEC 411 - Undersealing Pavement

Undersealing Pavement MSP-38E 06/98

MSP38E

SEC 616 - Traffic Control Plan

No Center Stripe Signing DSP-95-01C 05/98

STRIPES

Revised to remove (Level Course) from title since intent is for use on any resurfacing project. DSP also rewritten to conform to new format.

SEC 620 - Pavement Marking

Raised Reflective Pavement Markers (Snowplowable) DSP-93-12G 06/98
REFLPAVE

Revised to include Nightline A250 for roadway usage.

White and Yellow Acrylic Waterborne Traffic Marking Paint MSP-94-06E 06/98
MSP9406E

SEC 622 - Pavement Surface Texturing & Removal

PCCP Diamond Grind Texturing MSP-96-19B 06/98
MSP9619B

Limited use. Only as approved by Materials Division.

SEC 1000 - Materials

Concrete for MSE Systems and Other Commercial Precasting Works 06/98
MSP-91-09A
MSP9109A

SEC 1045 - Paint for Structural Steel & Wood

Aluminum Epoxy-Mastic Primer MSP-92-07C 06/98
MSP9207C
Aluminum Sulfonate/Polymer Topcoat 06/98
MSP9605A
Aluminum Sulfonate/Polymer Paint 06/98
MSP9606A

ADDITIONS:

MISCELLANEOUS

Disadvantaged Business Enterprise Contract Provision DSP-98-08 05/98
DBEPROV

Use this JSP when federal jobs are let in combination with state jobs.

SEC 620 - Pavement Marking

Acrylic Copolymer Fast Dry Traffic Marking Paint MSP-98-08 06/98
MSP9808

SEC 1018 - Fly Ash for Concrete

QC/QA Certification Acceptance of Fly Ash MSP-98-05 05/98
MSP9805

ATTENTION PROJECT MANAGERS: This JSP should be included in all projects specifying cement or fly ash.

SEC 1019 - Cement

QC/QA Certification Acceptance of Cement MSP-98-03 05/98
MSP9803

ATTENTION PROJECT MANAGERS: This JSP should be included in all projects specifying cement.

SEC 1045 - Paint for Structural Steel and Wood

Gray Epoxy-Mastic Primer MSP-98-04 05/98
MSP9804

ibo