

# Design Standards Letter

**Letter Number: G-2001-06**

**Letter Date: 03/30/2001**

**Effective Date: 04/01/2001**

**Section/Plan No.: G102, G105, G108, G203, G403, G501, G606, G616, G620, G806**

**Subject: Revisions to Job Special Provisions**

**Body**

-----  
 Questions concerning the distribution of revisions to job special provisions should be directed to General Headquarters, Design Standards Section, telephone number (573) 526-2924 or (573) 751-4659.

NOTES	EXPLANATION
1	The following listing shows the additions, revisions and deletions made to the General Headquarters Job Special Provisions between January 1 and March 31, 2001.
2	Current Job Special Provisions can be viewed on the MoDOT Web Page at <a href="http://www.modot.state.mo.us/business/business.htm">http://www.modot.state.mo.us/business/business.htm</a> under the heading "Standards and Specifications".
3	Designers, consultants and construction personnel can quickly access the latest revisions of the Job Special Provisions by viewing the AGC Updates in MoDOT's JSP Lotus Notes database. The JSPs compiled in the AGC (Associated General Contractors) Updates are in revision mode so that the viewer can easily identify the changes made to the JSP.

SECTION	DESCRIPTION OF REVISION	EFFECTIVE DATE
<b>SEC 0000</b>	<b>MISCELLANEOUS</b>	
	<b>Supplemental Revisions DSP-01-01B5</b>	<b>05/2001</b>
	This DSP was revised on five occasions: revised Certification of Blasters (B1); revised Embedded End Section (B2); Revised Section 105.16.3 through 105.16.5, 109.7.3, 109.9.1 and 109.13(h), and 1057.1 (B3); revised instruction pertaining to the revisions of Sections 105.16.3-5 (B4); and revised Section 109.0 and 109.13. (B5)	

<b>SEC 0102</b>	<b>BIDDING REQUIREMENTS AND CONDITIONS</b>	
	<b>Asphalt Binder Maximum Allowed Payment DSP-99-07M</b>	<b>04/2001</b>
	Revised the prices of Asphalt binder grades in January and March 2001, (L) and (M) respectively.	
<b>SEC 0105</b>	<b>CONTROL OF WORK</b>	
	<b>Division 100 Revisions for Non-Complex Projects DSP-97-06B</b>	<b>04/2001</b>
	Revised Section 105.16.	
	<b>Utilities DSP-93-26D</b>	<b>03/2001</b>
<b>SEC 0108</b>	The column entitled "Status of Work as of date" renamed "Anticipated Relocation Completion Date". Instructions for the categorization of projects.  <b>PROSECUTION AND PROGRESS</b>  <b>Working Day Count for Signals and Lighting DSP-90-05B</b> Increased the time before the count of working days is to begin from 90 to 104 days (two weeks). This is to accommodate delivery delays of signal and lighting poles.	<b>06/2001</b>
<b>SEC 0203</b>	<b>ROADWAY AND DRAINAGE EXCAVATION</b>	
	<b>Embankment in Place (Contractor Furnished Borrow) DSP-93-34J</b>	<b>05/2001</b>
	Revised Section 2.0, by adding paragraph under Option 2 pertaining to borrow sites that are not contiguous to MoDOT right-of-way and thus are regulated as separate land disturbance sites under the Missouri Clean Water Law.	
<b>SEC 0403</b>	<b>ASPHALTIC CONCRETE PAVEMENT</b>	
	<b>Superpave Asphaltic Concrete Pavement MSP-95-03Y</b>	<b>05/2001</b>
	Section 6.0 revised.	
<b>SEC 0501</b>	<b>CONCRETE</b>	
	<b>Epoxy Polymer Concrete Overlay MSP-00-01</b>	<b>05/2001</b>
	A new JSP adopted from Bridge by Materials.	
<b>SEC 0606</b>	<b>GUARDRAIL AND GUARD CABLE</b>	

	<b>Crashworthy End Terminal DSP-99-09E</b>	<b>05/2001</b>
	Under Section 2.3, ABSORB 350 added to Type C listing.	
	<b>Guard Cable 3-Strand DSP-01-07</b>	<b>02/2001</b>
	New JSP for installation of 3-strand guard cable.	
<b>SEC 0616</b>	<b>TRAFFIC CONTROL PLAN</b>	
	<b>Directional Indicator Barricade DSP-98-15B</b>	<b>02/2001</b>
	Revised or added Sections 2.1 through 2.5.	
	<b>Traffic Barrier Delineator DSP-98-20B</b>	<b>06/2001</b>
	Revised Section 3.0 to read "delineators shall be placed...every 25 feet (7.5 m)..." instead of 20 feet (6.0 m).	
<b>SEC 0620</b>	<b>PAVEMENT MARKING</b>	
	<b>Acrylic Copolymer Fast Dry Traffic Marking Paint MSP-98-08E</b>	<b>05/2001</b>
	Materials Engineering revised Sections 2.5, 2.6 and 3.2 pertaining to shelf life, age, and pounds per gallon, respectively.	
<b>SEC 0806</b>	<b>EROSION AND SEDIMENT CONTROL</b>	
	<b>Lightweight Erosion Control Blankets MSP-97-13A</b>	<b>02/2001</b>
	Deactivated the JSP.	