

Design Standards Letter

Letter Number: G-2003-05

Letter Date: 10/09/2003

Effective Date: 10/09/2003

Section/Plan No.: G403, G502, G806

Subject: Revisions to Job Special Provisions

Body

 Questions concerning the distribution of revisions to job special provisions should be directed to General Headquarters, Design Standards Section, Michael M. Qutami (573) 526-4331 or Bruce Green (573) 751-9248.

NOTES	EXPLANATION
1	The following listing shows the additions, revisions and deletions made to the General Headquarters Job Special Provisions between April 1, 2003 and September 30, 2003.
2	Current Job Special Provisions can be viewed on the MoDOT Web Page at http://www.modot.org/business/jobspecialprovisions.htm under the heading "Standards and Specifications".
3	Designers, consultants and construction personnel can quickly access the latest revisions of the Job Special Provisions by viewing the AGC Updates in MoDOT's JSP Lotus Notes database. The JSPs compiled in the AGC (Associated General Contractors) Updates are in revision mode so that the viewer can easily identify the changes made to the JSP.

SECTION	DESCRIPTION OF REVISION	EFFECTIVE DATE
SEC 0000	MISCELLANEOUS	
	Supplemental Revisions DSP 03-01D2	11/2003
	On the direction of Construction/Materials and to reflect new revisions, waivers & other AASHTO requirements referenced in Sections 1015.2.2 and 1057.1.03. Deleted all of Sec 1015.2.2 and substituted a new Sec 1015.2.2. Deleted all of Sec 1057.1.3 and substituted a new Sec	

	1057.1.3.	
	Supplemental Revisions DSP 04-01A	01/2004
	Delete all of Sec 303 and substitute a new Sec 303. The rock base thickness is reduced from 24” to 18”. This is the result of VE study and the on going efforts to improve process and save tax dollars. Delete all of Sec 626 and substitute a new Sec 626. The changes to the size and location of shoulder rumble strips (SRS) are the result of a UMR study done on the rumble strips in MO.	
SEC 0001	AAA- Check List	
	AAA- Checklist	10/2003
	Updated to include more changes to Standards since the previous checklist.	
SEC 0403	ASPHALTIC CONCRETE PAVEMENT	
	Superpave Asphaltic Concrete Pavement MSP-95-03Z	09/2003
	Added Sec 2.2.3.1.2	
	This section limits the amount of non-carbonate aggregate allowed in design level B mixtures containing limestone coarse aggregate.	
SEC 0502	Portland Cement Concrete Pavement	
	Pavement Specification for Alternate Bids DSP-03-10	11/2003
	All alternate pavement jobs need to have concrete QC/QA requirements similar to that with QC/QA superpave. Sections 403, 501, 502 were revised and combined into this new DSP- 03-10 for use in the alternate pavement projects.	
SEC 0806	Erosion and Sediment Control	
	Geosynthetic Reinforced Soil Slope System MSP-97-09B	09/2003
	Added two pre-qualified suppliers to Sec 2.0	